







Hydraulic and morphological modelling of the common SRB-CRO stretch of the Danube River



Republic of Serbia Ministry of Construction, Transport and Infrastructure **Directorate for Inland Waterways**





Modelling Components with time frame estimates



- 1D hydraulic model for the entire Serbian and Croatian common Danube stretch (3-4 months)
- Redefinition and prioritization of navigational bottlenecks (1-2 months)
- Definition of parameters for the multi-criteria analysis (1-2 months)
- Definition of alternative solutions for prioritized sectors and 2D hydrodynamic and morphological modelling (3-4 months)
- Development of the integrated study on alternative solutions and definition of next steps for future investments (last 6 months).

Starting in September 2023, the modeling procedure is expected to last a total of 12 months. Currently, a tendering procedure is being held in Serbia to select the most qualified candidate for the execution of this contract.

In the meantime, all relevant data that will be used for modeling are collected via the monitoring process.







allo.

Република Србија Министарство грађевинарства, саобраћаја и инфраструкуре Дирекција за водие путеве Београд, Француска 9 Број: 20,50 Дятум: 09.05.2023	Plovput's letter of support to the consortium
ЧЛАНО	ОВИМА КОНЗОРЦИЈУМА:
ОИКОН д.о.о. ХИДРОИНГ д.о.о.	Трг сеньских ускока 1-2 10020 Загреб Тадије Смичикласа
епублика Србија иникарство грађевинарства, вобраћаја и инфраструктуре преклија за водие путеве соград, Француска 9	lication regarding ned hydrographic measures der police)
рој: 20/40 атум: 21.04.2023.	
МИНИСТАРСТВО УГ ДИРЕКЦИ Управа граз Одељење за гра	IУТРАШЊИХ ПОСЛОВА А ПОЛИЦИЈЕ ничне полиције ницу - Начелнику Булевар Михајла Пупина 2
Гредмет: Обавештење о хидрографски km 1295+500 – km 1433+100	11000 Београд им мерењима реке Дунав на деоници

Поштовани

На основу Споразума Владе Републике Србије и Владе Републике Хрватске о пловидби пловним путевима на упутрашњим водама и њиковом техничком одржасавиу, прослеђувом Вам Обавентење о хидоргафском меренку реке Дунав од кт 1295-500 до km 1433+100 које ће се обавити у оквиру пројекта "Припрема FAIRway 2 радова на коридору Рујан-Дунав", који заједнички реализују Министарство мора, промета и инфраструктуре Републике Хрватске, Управе инфраструктуре Републике Србије. Копију Обавентења можете наћи у прилогу.

Coordination activities during April and May 2023

- Plovput issued a letter of support to the members of the consortium with the aim of easier obtaining the necessary permits and instructions from the competent institutions.
 - Agreed positions of end points and directions of cross section profiles at a mutual distance of 100m, which will be used for the needs of hydrographic measurements.
- Notifications regarding planned hydrographic measures were sent to the port authorities in the Danube common sector, as well as the border police.
- One online session with consortium representatives were held. The exchange of information is still going on.









Decision-making process used to evaluate and prioritize multiple options based on a set of criteria.



5th Stakeholder's Forum Meeting (online) Wed, **07. June 2023** (09:30-11:00 CEST) By considering various factors and their tradeoffs, MCA enables more informed and transparent decision-making.

STAKEHOLDERS

FORUM

Slide 4



Multi-criteria analysis (MCA) on critical sector "Bogojevo"



Options defined prior to the execution of the 2D modelling			
Option 1	Construct a side channel closure bund at km 1,365.5, dredging at km 1,363.5 and 1,362		
Option 2	Dredging		
Ontion 3	Sills and reconstruction of bank protection		

Option 4 Similar to option 1, but chevrons at right bank upstream of km 1,365.8 instead of closure bund

The presented options were evaluated and screened based on three criteria: *effectiveness, environmental impact and cost,* in order to determine which options would be subject to 2D modeling.

Screening of the options

Based on the information presented the options have been listed in Table 12.2. From the evaluation and screening of the options it is decided to further investigate and model the option 1 and 4.

effectiveness, mental impact ost, in order to which options

able 12.2. Sector #09 - Screening of options

Option	Effectiveness	Environment	Cost
1	+		0
2	-	0	0
3	-	+	-
4	0	+	0

Extracted from 2013 FEASIBILITY STUDY – Preparation of Documentation for River Training and Dredging Works on Selected Locations along the Danube River in Serbia

Delegation of the European Union to the Republic of Serbia EuropeAid/129691/C/SER/RS









Effects of newly built hydrotechnical infrastructure on the Danube in Serbia





- Hydrotechnical structures have been built in three of the six critical navigation sectors to improve navigation conditions.
- **Chevrons** were built on two critical sectors (Futog and Preliv) the first hydrotechnical structures of this type on the Danube.
- The representative of Plovput will give a presentation of the effects of these structures, mainly in a morphological sense, at the next SHFM meeting in September 2023.
- A discussion on this topic within SHFM could be an excellent starting point to the following modeling process.









Thank you for your kind attention

Ljubisa Mihajlovic, BSc Civil Eng. ljmihajlovic@plovput.rs